

# QUOTATION

Abingdon TC (SL\_ABING001-C)  
 Abingdon TC  
 Abingdon on Thames  
 Oxfordshire  
 OX143JE  
 GBR

**Quotation Date**  
 19 Jul 2024

**Expiry**  
 30 Aug 2024

**Account Number**  
 SL\_ABING001-C

**Quotation Number**  
 10118

**Reference**  
 KS Victoria Road

**VAT Number**  
 256 4018 13

Externiture Ltd  
 Unit 3 Daytona Drive  
 Thatcham  
 Berkshire  
 RG19 4ZD  
 UNITED KINGDOM  
 Tel: 01635 862100

## Shelter upgrade - Victoria Road on Ock Street

Nicky

Shelter upgrade for Victoria Road Eastbound. Stop ID – OXFATAJW on Ock Street

As discussed this is the suggested configuration, although it can easily be changed if required:

3 bay Mono living sedum roof shelter with a foot print of 3.673 x 1.375m. To be set at the front of path so passengers are facing the building when seated.

The side panels are full end panel on approach and half end panel on exit allowing for easier movement to board. The shelter is set back 450mm minimum from the kerb edge and will be located leaving 2m from the exit end panel to the bus stop pole. All panels are 6mm toughened glass with a mid rail and a 2 bay bench seating with handles, leaving one space for standing passengers or buggies or wheelchairs. Bench seating is by far and away more popular than perch

For the shelters to be fully inclusive for all passengers, we strongly recommend a contrasting mid rail, seating and poster cases. The vast majority of all shelters manufactured now have a contrast as this greatly assists those with visual impairment or early onset dementia as is greatly welcomed by user groups. The shelter is RAL9005 black currently

As an option we could supply solid aluminium lower panels which would be more durable as the panels nearest the road – there is a slight premium for this

No traffic management is required as it is in a long layby so standard chapter 8

Lead time 10 weeks from confirmation. Cost is for supply and installation and reinstatement

Sedum Green Roofs are hardy and generally considered to be maintenance free. However, being a living entity, we recommend a yearly application of slow-release fertiliser and a check for weeds. This is best carried out in Spring. Maintenance could be required especially if severe or abnormal conditions persist.

Description	Quantity	Unit Price	VAT	Amount GBP
To supply 3 bay FEP/HEP shelter with a living roof to Victoria Road EB	1.00	4,773.13	20%	4,773.13
Installation and reinstatement	1.00	1,225.00	20%	1,225.00

Description	Quantity	Unit Price	VAT	Amount GBP
			Subtotal	5,998.13
			Total VAT 20%	1,199.63
			<b>TOTAL £</b>	<b>7,197.76</b>

Full Terms and Conditions are available on request